

CONTRACT NO: IN/010/2019RE

FOR UNIVERSITY OF VENDA

ROADS INFRASTRUCTURE: UNIVEN TO PUNDA MARIA ROAD(R524)

**SCHEDULE E: ELECTRICAL WORKS**

Brought Forward					
<b>6</b>	<b>EXCAVATION AND TRENCHING</b> For the Supply and Labour of the following: Trenching for LV Cable 1000mm x 450mm wide (Including Backfill) Soft Ground	m	1000		
	Pickable ground	m	1000		
	Hard Rock	m	100		
	Danger Tape installed in Trenches	m	2100		
	Concrete cable markers	e.a	45		
	110mm PVC Cable sleeve	m	120		
<b>7</b>	<b>STREETLIGHTS</b> For the Supply, delivery to Site and Installation of the following Streetlight Units complete as per Specification:				
	Street Light Luminaire 27W LED Lume Double BRKT Piano Type, complete with base plates and Circuit Breaker MCB Including connection to the 25mm <sup>2</sup> Cable/ or complete wiring of Street Light.	e.a	37		
	Street Light Luminaire 27W LED Lume Double BRKT Piano Type, complete with base plates and Circuit Breaker MCB Including connection to the 25mm <sup>2</sup> Cable/ or complete wiring of Street Light.	e.a	13		
<b>8</b>	<b>WIRING ON THE POLE</b> 600/1000V grade PVC insulated stranded copper conductors compete with terminations and accessories				
	2,5mm <sup>2</sup> PVC insulated stranded copper conductors	m	2600		
	1.5mm <sup>2</sup> Stranded bare copper earth wire	m	1300		
<b>9</b>	<b>TESTING AND COMMISSIONING</b> Supply all Test equipment and Labour for Testing, Commissioning and Adjustment at Completion, as well as being in attendance for any Inspections and Tests that the Engineer may call for. All Eskom Standards and specifications will apply	Prov sum	1	R R24 000	R24 000.00
Total Carried Forward					