

CONTRACT NO: IN/010/2022

FOR UNIVERSITY OF VENDA
ROADS INFRASTRUCTURE: UNIVEN TO PUNDA MARIA ROAD(R524)

SCHEDULE B: ROADWORKS

SECTION
1500

Number	Item Description	Unit	Quantity	Rate	Amount R
15.00	ACCOMMODATION OF TRAFFIC				
15.01	Accommodating traffic and maintaining temporary deviations	km	0.39		
15.02	Earthworks for temporary deviations				
	(a) Shaping of temporary deviations	km	0.40		
	(b) Cut and borrow to fill	m ³	276.20		
	(c) Cut to spoil	m ³	2 727.70		
B15.03	Temporary traffic-control facilities				
	(a) Flagmen	man-day	2.00		
	(b) Portable STOP and GO-RY signs	No			Rate Only
	(d) Amber flicker lights	No			Rate Only
	(e) Road signs, R- and TR-series, (1200mm dia.)	No	6.00		
	(f) Road signs, TW-series, (1500mm sides)	No			Rate Only
	(g) Road signs, STW-, DTG-, TGS- AND TG-series (excluding delineators and barricades)	m ²	4.00		
	(h) Delineators (TW 401 and TW402):				
	(i) Single (TW 401 and TW402) (250mm x 1000mm)	No	40.00		
	(ii) Mounted back to back (TW 401 and TW402) (250mm x 1000mm)	No	250.00		
	(i) Single (TW 401 and TW402) (250mm x 1000mm)	No			Rate Only
	(j) Traffic cones (size indicated)	No	50.00		
	(i) Moveable barricade/road sign combination	No	14.00		
	(m) Two-way communication devices	No	6.00		
	(n) Other traffic control measures ordered by the engineer	No	4.00		
	(i) Provision of other traffic control measures	Prov sum	1.00	150 000	R150 000.00
	(ii) Handling costs and profit in respect of sub-item B15.03(n)(i)	%	150 000		
15.04	Relocation of traffic-control facilities	L/sum	1.00		
Total Carried Forward					